

ADDENDUM NUMBER ONE  
COLLEGE AVE. WATERLINE REPLACEMENT  
PEMBERVILLE, OHIO  
PROJECT NO. 10E08931  
October 21, 2019

BID OPENING: Wednesday October 30, 2019 at 1:00 PM local time at the Pemberville  
Village Hall, 115 Main Street, Pemberville, OH 43450.

**PLAN SET**

**SHEET 3**

Add the following note:

“ROCK EXCAVATION:

Soil Borings and as-built drawings of previous projects that are made available to determine the depth of bedrock are only applicable at the locations shown. It is the contractor’s responsibility to verify depth and quantity of bedrock to be removed. Payment for rock removal shall be included in the unit bid price per foot for the pertinent water line pipe item. No extras will be awarded for rock excavation.

Rock excavation shall be defined as removal of material that cannot be removed by hydraulic tracked excavator or similar type equipment. Rock excavation for trenches shall be extended to a minimum depth of 6 inches below pipe invert and to a minimum width of pipe O.D. plus 12”.

The contractor shall propose the method of rock excavation. The method shall be approved by the engineer.

The contractor is responsible for any property damage caused by his rock excavation methods. The Village of Pemberville and the Engineer assume no liability or responsibility for such damages. Operations entailing the use of hammers or compactors outside the hours of 8:00 am and 5:00 pm or those hours allowed by local ordinances shall be prohibited.”

On the “RESTRAINED JOINT TABLE”, change the Minimum Distance Restrained in Each Direction from Fitting for the 5-5/8 Degree Vertical Bends as follows:

6” VERT = 5’	18” VERT = 13’
8” VERT = 6’	20” VERT = 15’
10” VERT = 8’	
12” VERT = 9’	
14” VERT. = 10’	
16” VERT = 12’	

## **BID DOCUMENTS**

### Section 00100 INSTRUCTIONS TO BIDDERS

On Page 00100-2 Section 2.6 “Other Project Related Information”

Add Sections 2.61 through 2.64 as follows:

- 2.61 Pemberville College Ave and Memorial Drive Sanitary Sewer As-Built Drawings from 1997 (Project 95-1722)
- 2.62 Pemberville Sewer Separation As-Built Drawing from 1999 – Sheet 52 (Project 92-1133)
- 2.63 Subsurface Soil Investigation Report from TolTest dated July 15, 1996 for Pemberville College Ave and Memorial Drive Sanitary Sewer project.
- 2.64 Geotechnical Subsurface Investigation Report from TTL dated October 2019 for Proposed Roadway Improvements - College Avenue and Hickory Street.

We have added that additional information in a Dropbox format. A link to our Dropbox containing this information is below:

<https://www.dropbox.com/sh/q4udon40jh542ow/AACoj6bFbOp0YwtGWCv7FVQda?dl=0>

You can also find this link on our website in the Project Bid List section at <http://fellerfinch.com/bid-list/> and by scrolling down to this project and clicking on the link for “Clarification No. 1”

END OF ADDENDUM #1